

Mr Lloyd Reynolds
New House Farm
Water Lane
Barnardiston
Suffolk
cB9 7TH
Tel: 07879339579
Email: Lloyd@onpointcarpentryandjoinery.co.uk

Keith
Melbourn parish council

Ref: Removal and
replacement of fence in
centre of the village

To remove, dispose of and replace the run down oak posts and rails in the centre of the village.

Material: Green oak

Section sizes:

50 no 135mm x 100mm posts 900mm long approximately 300mm in the ground

48 no 75mm x 55mm rails mostly 2000mm long

We will join two together and cut the correct angles in place of the three corners that currently have two sat together

All morticed and Tenoned together and held tight with oak dowels

All posts concreted in to ensure they don't sink etc

Post detail the same as existing (curved tops)

Total: £5,920.00

VAT: £1,184.00

Total inc VAT: £7,104.00

Subsequent additions and/or amendments to this project (not detailed within the quotation above), will be subject to additional costs and quoted separately. Any additional work not quoted for will be charged at £27.50 per hour per person + VAT