



TREE  SURGERY LTD

63 Winfold Road, Waterbeach, Cambridge, CB25 9PR
Tel / Fax: 01223 861698 info@acaciatreesurgery.co.uk
www.acaciatreesurgery.co.uk



Ref. kmf MELB PC 12.3.21 cf144

Ms Sophie Marriage
Assistant Clerk
Melbourn Parish Council

12 March 2021
assistantclerk@melbournpc.co.uk

Dear Sophie

Orchard Road, Melbourn

Thank you for your enquiry regarding tree work at the above site and further to our inspection of 10 March, we have pleasure submitting our recommendations in the attached schedule.

In all instances, we exercising vehicular and pedestrian management in the form of traffic lights to ensure the safety of the public, taking great care to avoid any damage to adjacent grounds and property, clearing all arisings to leave each site in a safe, clean and tidy condition.

The costs are quoted exclusive of but are subject to VAT.

Please refer to our remaining terms and conditions stated overleaf and if you have any further query, please do not hesitate to contact us. Meanwhile, assuring you of our best attention.

Yours sincerely

Karen

Karen Cole
Office Manager

**SPECIALIST
TREE CARE
AND SURGERY**

**TREE PRUNING
AND SHAPING**

**TREE
PLANTING AND
HEDGE
TRIMMING**

**TREE FELLING
AND TREE
STUMP REMOVAL**

**COSTING
SURVEYS AND
INSURANCE
REPORTS**

SCHEDULE OF WORK FOR MELBOURN PC AT ORCHARD ROAD
 Inspected by Cliff Freed on 10 March 2021

Ref	Species	Work requirements	Cost
8 PROTECTED TREES IN HIGHWAY VERGE opp junction to ORCHARD GATE			
All of the 8 trees have ivy encroachment into the crowns. We have provided two options to manage this evasive growth and prevent full encroachment, as this coverage will conceal defects and increase wind resistance. The severing of ivy option involves cutting a 1m band around the base of the trunk; the removal option involves carefully removal of ivy down to base level.			
T1	SYCAMORE	a) sever ivy and remove basal growth; b) remove ivy and basal growth; c) repollard, inc remove ivy and basal;	£150.00 £550.00 £700.00
T2	SYCAMORE	a) sever ivy; b) repollard and remove ivy;	£ 35.00 £400.00
T3	SYCAMORE	a) sever ivy and remove basal growth; b) repollard and remove ivy and basal;	£125.00 £500.00
T4	SYCAMORE	a) sever ivy and remove basal growth; b) repollard and remove and basal;	£160.00 £700.00
T5	ASH	a) sever ivy and cut back ivy to kerb edge; b) remove ivy; c) reduce height by 3ms and laterals by 2ms to balance and remove ivy;	£140.00 £475.00 £960.00
T6	ASH	a) sever ivy and raise low crown to 5ms all round; b) remove ivy and raise crown to 5ms all round; c) reduce height by 2.5ms, remove ivy and raise crown to 5ms all round;	£180.00 £260.00 £400.00
T7	ASH	a) sever ivy and remove basal growth; b) remove ivy and basal growth; c) reduce height by 2.5ms and laterals by 3ms to balance, remove ivy and basal;	£125.00 £580.00 £800.00
T8	ASH	Recent work taken place, no further work required	
Due to proximity of trees to road, traffic lights will be required for options (b) or (c); pls note that all vehicles parked on opposite side of road would have to be moved for duration of works ~ approx 4 to 5 days.			£500.00