

Shelford – quotation breakdown

Jobs have been identified at the pavilion and Shelford Heating have quoted for these.

Thank you for your email.

The costs we have provided are budget costs, and therefore you will be charged for the materials used and time spent on site. We have it noted in our quotation that:

The Budget cost as follows will be fully calculated by the time expended on site by our Representatives and the Associated Parts purchased or utilised from our Stock holding which may decrease as we generally are cautious in presentation of our time and material allowances, however it can also have the negative effect especially if a situation arises that was not evident at the initial survey stage.

However, please see below the costs we have allowed:

- 1. To Supply and Install 15mm copper pipe for Plumbing Services and Adjusting Cold fill to Urinal*
We have allowed £56.03 + VAT to supply and fit the above
- 2. To Supply and Install 3no. Cisterniser Infrared Flush Control Valves Mains or Battery Operated.*
We have allowed £657.20 + VAT to supply and fit the above.
- 3. To Strip and Clean the 5no. TMV, adjust and set temperatures. Unfortunately we will be unable to disinfect HWSV.*
We have allowed labour only at a cost of £367.50 + VAT.
- 4. To Inspect Loft Space Pipework Insulation.*
We have allowed labour only at a cost of £98.00 + VAT.
- 5. To Supply and Install Insulation to Pipework Within Boxing in Disabled WC. 15mm X 9mm X 2000MM.*
We have allowed £52.73 + VAT to supply and fit the above.

If you have any questions or queries, please do not hesitate to contact us via email or on 01223 833426.

Kind regards

*Amy Wilson
Installation Coordinator*

Job 1) Urinals ...

Shelford – quotation breakdown

Job 2) The legionella risk assessment recommended fitting automatic flushing or flushing through manually manual flushing through is taking place so the installation of automatic flushing valves is not needed.

Job 3) The legionella risk assessment recommended that all TMV's should be serviced annually.

Jobs 4&5) The legionella risk assessment recommended installing insulation to pipework as a high priority job.