## Excavations

Little Hands Nursery, Melbourn

- 001 Floor saw existing concrete slab; ne 150mm say
- 002 Break out ditto; disposal offsite
- 003 Remove shrubs, foliage from from area; inc disposal
- 004 Excavate by machine to depth ne 450mm say; inc. disposal of excess onsite
- 005 Level and compact base of excavation
- Excavate by machine for pipe trench; ne 700mm deep say for drainage pipe; backfill on completion and reseed 006
- affected ground only; inc. disposal of excess
- 007 Level and compact base of excavation
- 800 Excavate by machine for soakaway; including disposal of spoil

## **Drainage Works**

- Supply & Lay new 110mm Polyethylene Pipework to ditto 009
- 010 Supply and lay well compacted granular bed & pipe surround
- 011 Supply and install Polystorm lite units; ne 70m3 volume say
- 012 e/o membrane to ditto; 300mm overlaps
- 013 Supply and lay granular surround to ditto; ne 100mm say
- Supply & Fit Channel Drain: B125 Loading; Plastic Channel & drain; ne 130mm Wide x 105mm Deep 014
- 015 Concrete C15; foundation to ditto; 150mm x 138mm
- Concrete Works for New Parking Area
- 016 Granular filling to beds ne 225mm deep
- 017 Level and compact ditto; ne 150mm intervals
- 018 e/o membrane to ditto; 300mm overlaps
- 019 Backfill with C40 roadmix concrete to form original Surface; brush finish; ne 225mm thick
- 020 e/o for brushed finish
- 021 e/o form work to ditto
- 022 e/o A393 rebar mesh; 2 layers
- 023 e/o 600mm dowel bar; as per Longitudinal joint detail; 10mm; @ 600mm c/c; inc. sleeve & cap
- 024 e/o movement joint filler board to ditto

**Total Value to Summary** 

71,002.09 +VAT

£

Pricing Notes

- We have assumed free and uninterrupted access to site with no delays to completing the work beyond our control

- We have assumed free and uninterrupted access to site with no delays to completing the work beyond our control
  We have allowed for the works to be done during normal working hours and in one continuous visit and have assumed no noise restrictions
  Standing time for reasons beyond the control of Semilong Services Ltd. will be charged as extra
  We have assumed that there is no restriction on the use of plant
  Specification of correte, reinforcement and depth has been assumed for pricing purposes; This estimate may be subject to revision once exact details are confirmed by Structural engineer
  We have made certain assumptions for pricing purposes. If proved incorrect Semilong Services reserve the right to reprice.
  Ye have made certain test 8 soakaways accelucialismos demend to be by others
  We have not allowed for anything not specifically stated within the above measure
  We have not allowed for anything not specifically stated within the above measure
  Ye forther services are found, that hinder the proposed works, Semilong Services reserve the right to reprice the works acccordingly
  We have allowed for the works accordingly
  We have not allowed for stated list of Normal peory resh tased screed; colour red. -deemed to be by others
  The Price is exclusive of VAT and will be valid for 28 days from the date shown unless stated