



Curtis & Sons

**SURFACING AND CIVIL
ENGINEERING CONTRACTORS**

VAT No. 855 2787 86



High Barns, Marlow Road, Cadmore End, High Wycombe, Bucks. HP14 3PP.

HIGH WYCOMBE: 01494 483184

David Curtis Jr: 07901 864183 - davidcurtistarmac@gmail.com

CUSTOMER ADDRESS:

Alex Coxall & Abi Williams

Melbourn Parish Council

Melbourn Community Hub

30 High Street

Melbourn SG8 6DZ



QUOTATION

Date: 2.4.2024

REF: MELBOURN PARISH COUNCIL - LITTLE HANDS CARPARK REINSTATEMENT

DESCRIPTION AND SCOPE

The work to be performed under this contract consists of the rehabilitation and reclamation of existing soiled/vegetation area as highlighted in Fig 1. All materials, construction and workmanship shall conform to manufacturers guidelines.

Works as discussed on site and attached with this description will be included in the price

PLEASE NOTE: the quote does not include any removing of asbestos or includes any soil tests this would need to confirmed before works commenced?

Duration time of works: 5 working days - 7.30am to 4pm

- Works area. 120m²
- Excavate the work area shown in dash line section (fig 1) to 250mm below ground level
- Reinstate 150mm of type one MOT, compressed at 75mm layers.
- Reinstate 50mm sharp sand.
- E50 Grid to suit area.
- Lay 20mm singe into grid system and compress.

Thank you for inviting us to advise and quote for the above works.

Regards David Curtis

UTR 2650169434 - NH 7954 55A

Curtis Surfacing

Bank: Lloyds - Acc: 13777662 - Sort: 30-99-50

Labour	£
Sub Total	£12,500.00
VAT	£2,500.00
Total	£15,000.00